Sample Work Breakdown Structure

- 1. Carpentry
  - 1.1. Gut the Kitchen
    - 6 hour(s)
    - R: Carpenter 1
  - 1.2. Build Custom Island
    - 1.2.1. Framework
      - 24 hour(s)
      - R: Carpenter 2
    - 1.2.2. Skin
      - 8 hour(s)
      - R: Carpenter 2
  - 1.3. Install Cabinets
    - 1.3.1. Base cabinets
      - 12 hour(s)
      - R: Carpenter 3
    - 1.3.2. Wall cabinets
      - 8 hour(s)
      - R: Carpenter 3
  - 1.4. Drywalling
    - 8 hour(s)
    - R: Carpenter 3
  - 1.5. Baseboards
    - 6 hour(s)
    - R: Carpenter 3
  - 1.6. Trim
    - 6 hour(s)
    - R: Carpenter 3
- 2. Plumbing
  - 2.1. Reroute sink hook up under window
    - 6 hour(s)
    - R: Plumber 1
  - 2.2. Install water lines to island
    - 6 hour(s)
    - R: Plumber 1
  - 2.3. Install gas to oven
    - 5 hour(s)
    - R: Plumber 2
  - 2.4. Install gas to stove
    - 2 hour(s)
    - R: Plumber 2
  - 2.5. Install waterline to refrigerator
    - 2 hour(s)
    - R: Plumber 1
- 3. Electricity
  - 3.1. Rewire
    - 16 hour(s)
    - R: Electrician
  - 3.2. Install new circuits
    - 6 hour(s)
    - R: Electrician
- 4. Install Appliances
  - 4.1. Stove
    - R: Plumber 1
  - 4.2. Microwave
    - R: Electrician
  - 4.3. Convection Oven
    - R: Plumber 1
  - 4.4. Fan
    - R: Electrician
  - 4.5. Garbage Disposal
    - R: Plumber 1
  - 4.6. Refrigerator
    - R: Plumber 1
  - 4.7. Lights
    - R: Electrician
  - 4.8. Sinks
    - R: Plumber 1
- 5. Countertops
  - 5.1. Island
    - 4 hour(s)
    - R: Counertop Installer
  - 5.2. Wall
    - 8 hour(s)
    - R: Counertop Installer
  - 5.3. Backsplash
    - R: Counertop Installer
- 6. Paint
  - 6.1. Post Dry Wall
  - 6.2. Post Carpentry
    - 6.2.1. Walls
      - 6.2.1.1. Coat 1
        - 4 hour(s)
        - R: Painter
      - 6.2.1.2. Coat 2
        - 4 hour(s)
        - R: Painter
    - 6.2.2. Trim
      - 6.2.2.1. Coat 1
        - 4 hour(s)
        - R: Painter
      - 6.2.2.2. Coat 2
        - 4 hour(s)
        - R: Painter
  - 6.3. Touch Up